

Request for Proposal: Inuvik Office - Install Fume Hood Clarification #1

Issued by:

Inuvialuit Regional Corporation (IRC)

107 Mackenzie Road

Inuvik, NT X0E 0T0

Deadline for submissions: February 13, 2026, 14:00 (2:00PM) MST



Clarification 01

Project:	DFO Inuvik Fume Hood Replacement	Date:	February 2, 2026
Project #:	0050058.00	Client:	Inuvialuit Development Corporation

No changes to the specification or drawing package has been made based on this clarification.

1.	Inquiry	The supplied Fume Hood is a Labconco model 2247300 with an Integral Blower, the drawings also show an inline fan EF-3 in the ceiling space ducted through the roof, the equipment schedule for EF-3 list a Twin City Fan & Blower Model TFE which is an exterior mounted unit. Please provide clarification on the Fume Hood exhaust venting.
	References	Refer to Drawing M03
	Answer	The integral blower is anticipated to have insufficient external static pressure for this application. The blower is to be removed from the fume hood and returned to the owner. EF-3 is to be installed in the ceiling space of the lab. This is detailed in the drawing package.

Attachments: N/A

Prepared by,

Williams Engineering Canada Inc.

DANIEL BROWN, P.Eng.
Team Lead, Mechanical

T 780.409.5300 C 587.982.0460
E dbrown@williamsengineering.com

End of Clarification 01

X:\01-Edmonton\Projects\0050058.00\50_Tender\0050058.00_DFO_Inuvik Hood Fan Replacment_Clarification_01.docx